

**17**  
**YANAM MUNICIPALITY**  
**YANAM**

**Name of work: Laying of C.C roads and drains in Ambedkar Nagar, Yanam**

**Schedule "A" - 1/2**

Sl. No.	Code No. & Description of Item.	Qty.	Rate in		Per	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	3.10.1 Earthwork in excavation in foundation trenches etc. in drains and channels etc. not exceeding 2 metres depth including dressing of bottom and sides of trenches stacking the excavated soil clear from the edge of excavation including disposal of surplus soil as directed within a lead of 30 metres - ordinary soil. As per clause no 303.3.7 at MOST specification	285.00 Cum			1 Cum (One Cubic Metre)	
2	2.28 Supplying and filling in plinth with river sand under floors including, watering, ramming consolidating and dressing complete.	27.00 Cum			1 Cum (One Cubic Metre)	
3	4.5.10 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40mm nominal size).	28.00 Cum			1 Cum (One Cubic Metre)	
4	4.5.3 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size).	136.00 Cum			1 Cum (One Cubic Metre)	

1	2	3	4	5	6	7
5	4.9.1 Centring and shuttering including strutting, propping etc. and removal of form work for - foundations, footings, bases for columns.	753.00 Sqm				1 Sqm (One Square Metre)
6	13.8.2 12 mm cement plaster of mix - 1:4 (1 cement : 4 fine sand)	683.00 Sqm				1 Sqm (One Square metre)
7	4.2D Providing and laying sand gravel mix 1:1 of 150mm consolidated thickness using 0.68cum of sand & 0.62cum of gravel for 1cum finished to a soaked CBR value of minimum 20 including cost and conveyance of sand and gravel to the work site and stacking to the standard departmental gauge for premeasurement, mixing the required quantities of sand and gravel, spreading watering and consolidation the mix by power roller rolling to achive the required proctor density including the labour charges for mixing, spreading, hire and fuel charges for power roller and all other tools and plants employed etc., complete. As per clause no 401 of MOT specification.	16.00 Cum				1 Cum (One Cubic Metre)
8	5.19 Providing, hoisting and fixing upto floor five level precast reinforced cement concrete in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centring, shuttering, finishing smooth with 6mm thick cement plaster 1:3 (1 cement : 3 sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size).	35.00 Cum				1 Cum (One Cubic Metre)
9	5.29.3B Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all Complete-Thermo mechanical treated bars(Tiscon/Vizag/lisco/Sail)	4,600.00 kg.				1 Kg. (One Kilogram)