

17
YANAM MUNICIPALITY
YANAM

Name of work: Providing approach road from Straw Board to Bheem Nagar flood bank road, Yanam

Schedule "A" - 1/3

Sl. No.	Code No. & Description of Item.	Qty.	Rate in		Per	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	3.10.1 Earthwork in excavation in foundation trenches etc. in drains and channels etc. not exceeding 2 metres depth including dressing of bottom and sides of trenches stacking the excavated soil clear from the edge of excavation including disposal of surplus soil as directed within a lead of 30 metres - ordinary soil. As per clause no 304.3.7 of Most specification	73.00 Cum			1 Cum (One Cubic Metre)	
2	2.28 Supplying and filling in plinth with river sand under floors including, watering, ramming consolidating and dressing complete.	11.00 Cum			1 Cum (One Cubic Metre)	
3	4.2D Providing and laying sand gravel mix 1:1 of 150mm consolidated thickness using 0.68cum of sand & 0.62cum of gravel for 1cum finished to a soaked CBR value of minimum 20 including cost and conveyance of sand and gravel to the work site and stacking to the standard departmental gauge for premeasurement, mixing the required quantities of sand and gravel, spreading watering and consolidation the mix by power roller rolling to achive the required proctor density including the labour charges for mixing, spreading, hire and fuel charges for power roller and all other tools and plants employed etc., complete. As per clause no 401 of MOT specification.	120.00 Cum			1 Cum (One Cubic Metre)	

1	2	3	4	5	6	7
4	4.93A Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth 3 wheeled steel roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type B screening and binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density - by manual means - Water bound macadam Gr-III with type B 11.2mm screening. (As per MoRTH specification, 4th revision	132.00 Cum			1 Cum (One Cubic Metre)	
5	4.5.10 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40mm nominal size).	11.00 Cum			1 Cum (One Cubic Metre)	
6	4.5.4 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering -All work upto plinth level 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40mm nominal size)	251.00 Cum			1 Cum (One Cubic Metre)	
7	4.9.1 Centring and shuttering including strutting, propping etc. and removal of form work for - foundations, footings, bases for columns.	276.00 Sqm			1 Sqm (One Square Metre)	

1	2	3	4	5	6	7
8	5.29.3B Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete - Thermo Mechanical Treated Bars -(TISCON / Vizag/iisco/sail)	4770.00 Kg.			1 Kg. (One Kilogram)	
9	7.23A Providing and fixing premoulded bitumen joint filler, for expansion joints including the cost of sealing compound and priming coat - 12 mm wide	3498.00 m/c			1 m/c (One Metre/C)	